

NEW MIRAMONTE RESIDENCE TBD JOHNSTON ROAD PLEASANTON, CA

BUILDING CODE CRITERIA

2022 CALIFORNIA BUILDING CODE (2021 IBC WITH STATE AMENDMENTS) 2022 CALIFORNIA MECHANICAL CODE (2021 UMC WITH STATE AMENDMENTS 2022 CALIFORNIA PLUMBING CODE (2021 UPC WITH STATE AMENDMENTS) 2022 CALIFORNIA ELECTRIC CODE (2021 NEC WITH STATE AMENDMENTS) CALIFORNIA ENERGY CODE, 2022 COUNTY OF CONTRA COSTA CONSTRUCTION ORDINANCES

Roof LL	20 /16 psf	
Attic LL	10 psf	
Floor LL	40 psf	
Wind Speed	110 mph	
Wind Exposure	C	
Site Class	D	
Seismic Design Category	D	
5D5	1.373	
V =	0.196W	
Importance Factor	1.0	

CONSTRUCTION TYPE: V-B OCCUPANCY TYPE: R-3

APN: 204-120-015-1 ZONED R-L

TOTAL LIVING AREA

COVER'D PORCHES 364 sf

 $\frac{282 \text{ sf}}{646 \text{ sf}}$

536 sf 3376 sf

2194 sf

GARAGE TOTAL AREA




FRONT ELEVATION

SCALE: 1/4" = 1'-0"

DATE
JUNE 2023
SCALE
AS SHOWN
DRAWN BY
K.S.WRIGHT
DWG FILE:
23.09

DRAWING NO. A1 SHT 1 OF 6 w/h HVAC attic access?



DATE
JUNE 2023
SCALE
AS SHOWN

DRAWN BY

DWG FILE: 23.09


DRAWING NO.


A2 SHT 2 OF 6

FOUNDATION NOTES:

- A. Provide R-19 insulation in all new floor areas U.O.N.
- B. Provide metal foundation vents per venting calculations on Foundation Plan. Do not block (e) vents.
- C. Provide solid blocking under walls that run perpendicular to floor joists. Provide double floor joists under walls running parallel to floor joists.
- D. Provide new crawl space access. Minimum 18" x 24". See plan for location. Use joist hangers as needed.







DRAWING NO.

A5
SHT 5 OF 6

PRE-MANUFACTURED ROOF TRUSSES


- A. Pre-fabricated timber trusses shall be designed and fabricated with ICC approved plate fasteners. Lumber used in trusses shall be Douglas Fir. Trusses shall be designed by a registered Civil Engineer, licensed in California; design calculations and shop drawings shall be provided for review by the engineer of record, then submitted to the Building Department.
 - I. Unless noted otherwise on the drawings, truss loading shall conform to the following:

Roof trusses:	Top chord loading:	DL = 17 psf LL = 16 psf	Top Chord shall be min 2x 6
	Bottom chord loading:	DL = 5 psf <u>LL = 10 psf*</u> TL = 38 psf	* Not simultaneous with top chord LL

- B. Truss manufacturer shall supply all hangers, clips, plates, blocks, bridging, and all other items relative to their units.
- C. All trusses shall be delivered to the site, bundle wrapped and piece-marked for locations. Trusses shall not be field cut.
- D. Connector plates: All connector plates shall be a minimum thickness of 0.036" and shall be of steel meeting the requirements of ASTM A446 Grade A as a minimum, hot dipped galvanized per ASTM A525, G60 coating (unless placed in highly corrosive environments).
- E. Girder trusses: Design special trusses for same criteria as standard trusses including the effects of tributary loads from in-framing members. See framing plan for truss layouts. The truss manufacturer shall submit the design and detail of all connectors required to transfer loads to the special trusses, U.N.O. on the plans.
- F. Collector trusses: Design special trusses for same criteria as standard trusses including the effects of lateral loads as noted on framing plans. See framing plan for truss layouts. The truss manufacturer shall submit the design and detail of all connectors required to transfer loads to the special trusses, U.N.O. on the plans.
- G. Provide minimum of (2) studs below the bearing points of all girder and hip trusses and carry down to foundation level, typical.
- H. Execution:
 - I. Inspect the installed work of other trades and verify that such work has been so installed as to allow rough carpentry to produce surfaces to the required design.
 - 2. Provide all permanent structural cross bracing to ensure overall rigidity of the diaphragm in accordance with the architectural and engineering plans for the structure.
 - 3. Cut all wood members for a tight fit. Do not shim. Erect all members straight, plumb, and accurately located.
- I. Install all backing, blocking and stripping required for the work of other trades.
- J. Brace all trusses and pre-fabricated wood joists during erection and after permanent installation.
- Review prior to installation: Prior to installation of trusses, two copies of the following materials bearing the approval of the Engineer of Record (Shaer-K Engineering) in the form of a separate letter must be submitted to the Building Official for review at least two weeks prior to frame inspection: (1) truss layout drawings; and (2) truss calculations and details showing axial and bending stresses and joint designs, clearly indicating that designs conform to the 2020 CBC.

ROOF PLAN

SCALE: 1/4" = 1'-0"



SCALE AS SHOWN

DRAWN BY
K.S.WRIGHT
DWG FILE:
2020.12

DRAWING NO.

A6